



CERN Safety Alarm Monitoring (CSAM)

4th LHC Controls Project Workshop

Luigi Scibile & CSAM project team

11/06/2003

4th LHC Controls Project Workshop

1



Summary Overview



- ◆ Major User Requirements
- ◆ Proposed architecture
- ◆ Major technical choices, outstanding issues
- ◆ Infrastructure requirements (location, technical services, control system services, communications ...)
- ◆ Plans for installation and commissioning
- ◆ Milestones for the work

11/06/2003

4th LHC Controls Project Workshop

2



Major User Requirements 1/2



- ◆ **For the Fire Brigade**
 - Safety alarm acquisition from all CERN safety zones.
 - Local monitoring from each safety zone
 - Central monitoring, archiving, display, reporting and configuration
 - Non-interruptible 24h/365d system based on redundant communication networks
 - Specific Human Computer Interfaces and tools for the alarm handling
 - Real-time monitoring of the correct functioning of all safety sub-systems.

11/06/2003

4th LHC Controls Project Workshop

3



Major User Requirements 2/2



- ◆ **For the Experiments and the other control rooms**
 - A safety alarm gateway to external systems
 - A flexible system architecture for the integration of the LHC and LHC Experiments future alarms.
 - A modular acquisition and local monitoring system based on standard industrial equipment
- ◆ **Availability requirements**
 - In order to meet the availability requirements of $\approx 99.8\%$ set by the AL3 Working Group, a Safety Integrity Level SIL 2 has been fixed.
 - A Supervision and monitors the availability of all sub-systems and generates performance reports.
- ◆ **Maintainability requirements**
 - integration in the Maintenance Manager System (MP5)


11/06/2003

4th LHC Controls Project Workshop

4



Proposed HW architecture




11/06/2003

4th LHC Controls Project Workshop

5

Proposed SW architecture



11/0

6



Major technical choices






- ◆ **No common mode of failure**
 - Power supply, Location, server, display, acquisition module, etc.
- ◆ **INB compliant system based on redundant transmission paths**
 - The NEW Technical Service network
 - The General Service network
 - The existing hard-wired links.

11/06/2003

4th LHC Controls Project Workshop

7






Infrastructure requirements




- ◆ Rack: re-use of old AL3 Racks
- ◆ Power supplies:



TCP/IP Network Infrastructure

Network connections summary for June 2003:
 New Service Network: 20 new connections
 General Network: 18 new connections





Plans for installation and commissioning



- ◆ SCR, TCR and Point 1.8-> Inst. 06/2003 - Comm. 10/2003
- ◆ Point 1 - Safety Zone 1 -> Inst. 12/2003 - Comm. 01/2004
- ◆ Point 2 - Safety Zone 2 -> Inst. 01/2004 - Comm. 02/2004
- ◆ Point 3.1 - Safety Zone 31 -> Inst. 02/2004 - Comm. 03/2004
- ◆ Point 3.2 - Safety Zone 32 -> Inst. 03/2004 - Comm. 04/2004
- ◆ Point 4 - Safety Zone 4 -> Inst. 04/2004 - Comm. 05/2004
- ◆ Point 5 - Safety Zone 5 -> Inst. 05/2004 - Comm. 06/2004
- ◆ Point 6 - Safety Zone 6 -> Inst. 06/2004 - Comm. 07/2004
- ◆ Point 7 - Safety Zone 7 -> Inst. 07/2004 - Comm. 08/2004
- ◆ Point 8 - Safety Zone 8 -> Inst. 08/2004 - Comm. 09/2004

11/06/2003

4th LHC Controls Project Workshop

17



Milestones for the work



- ◆ Detailed design completed by September 2002
 - Safety validation of proposed architectures
- ◆ System realisation completed by January 2003
 - Practical integration of all the safety systems in CSAM
- ◆ Pilot installation in SM18 in June 2003
- ◆ CSAM running in background until October 2003
- ◆ Acceptance Testing by October 2003
- ◆ If acceptance successful
 - ◆ CSAM OPERATIONAL in SCR and TCR
 - ◆ After First Acceptance - One LHC point per month

11/06/2003

4th LHC Controls Project Workshop

18



Thank you for your attention!



<http://st-proj-csam.web.cern.ch/st-proj-csam/>

11/06/2003

4th LHC Controls Project Workshop

19