

3

21.03.2002

4

Fast cycle changes

Fast Cycle changes imply that :

- Settings for different cycles must be stored in the front-ends...
- S All systems must be ready to execute any stored cycle.
- S The information about which cycle to run is distributed by the machine timing system.

applies also to the hardware interlock logic !

we must consider fail-safe handling of machine timing inside many systems generating hardware interlocks & inside the interlock system itself !

21.03.2002 LHC-CP WS 2002 / J. Wenninger 21.03.2002 LHC-CP WS 2002 / J. Wenninger **Extraction Interlocks Status** The interlock situation has been reviewed with the "actors" that are The extraction interlock system must know which cycle is involved today (BI, BT, PO, CO) to identify played because the extraction channels are shared : S Present limitations. § Future developments. LSS4 : CNGS/LHC (TI8). LHC + CNGS S Critical issues : (FE only) LSS6 : FT/LHC (TI2). • Timing. • Power converter surveillance (inside ROCS ?). Vacuum (sectorization). Beam quality handling. Interlock conditions must North Area LHC interlock & beam request handling. change with cycles ! SE only Some ideas have emerged, but more work is required before a West Area + LHC solution emerges. (SE + FE)**K** 21.03.2002 LHC-CP WS 2002 / J. Wenninger 21.03.2002 LHC-CP WS 2002 / J. Wenninger

SPS Emergency Beam Dump

The present SPS beam dump system does not know about SPS cycles, but :

- Some form of cycle handling is already performed by the systems providing some input channels (Beam losses).
- S Clean cycle handling is limited so far due to missing information (precise beam type...)
 - Timing system must provide more info in the future !

For the future

- S The present emergency beam dump system could "survive" into the multi-cycling area, but :
 - o spare parts are rare.
 - o not much room for new inputs.
- S A new system must be put in place in the coming years.

Timescales & outlook

- 2002 : proposal for a conceptual design.
- <u>Summer/fall 2003</u>: extraction tests TT40 / TI8.
 § Ideally : test of a 'meaningful' prototype.
 § It is not clear if a prototype can be build within that timescale !

• Most urgent problems / decisions :

- S NO manpower is presently available to build the SPS system.
- S A proposal to form a single interlock section for all machines has been made, but the 'home-group' and manpower resources of this section are not finalized...

21.03.2002

LHC-CP WS 2002 / J. Wenninger

9